

SCHEDULE OF MAXIMUM PIPE DEFLECTION

Maximum Offset per 18 FT Length of Pipe, Inches

NOMINAL PIPE SIZE INCHES	PUSH-ON JOINTS	RESTRAINED PUSH-ON JOINTS	MECHANICAL JOINTS	LOCKED M.J.
3	15	12	25	9
4	15	12	25	8
6	15	12	21	6
8	15	12	16	4
10	15	12	16	4
12	15	12	16	3



VILLAGE OF INDIAN HILL
DEPARTMENT OF WATER WORKS

APPROVED *[Signature]*
DATE November 2011

SPECIFICATIONS
WATER MAIN
AND APPURTENANCES

DRAWING NO.

WW-117